

Evaluation of Existing Information
on INTOR Related Research and Development

A.F. Knobloch

IPP 4/196

March 1981



MAX-PLANCK-INSTITUT FÜR PLASMAPHYSIK

8046 GARCHING BEI MÜNCHEN

FORMATION ON
MAX-PLANCK-INSTITUT FÜR PLASMAPHYSIK
GARCHING BEI MÜNCHEN

Evaluation of Existing Information
on INTOR Related Research and Development

A.F. Knobloch

IPP 4/196

March 1981

*Die nachstehende Arbeit wurde im Rahmen des Vertrages zwischen dem
Max-Planck-Institut für Plasmaphysik und der Europäischen Atomgemeinschaft über die
Zusammenarbeit auf dem Gebiete der Plasmaphysik durchgeführt.*

A.F. Knobloch

March 1981

Abstract

During the INTOR workshop sessions (phase I) an attempt was made to arrive at a preliminary and qualitative assessment of INTOR relevant R+D in Europe, Japan, United States and USSR. All four delegations contributed in an iterative way.

The results achieved so far have been used to compare the actual situation with an idealized schedule for a possible INTOR realization. Also they enable a preliminary insight into the degree of completeness in R+D required for INTOR to be expected in various partner combinations.

Pending a detailed evaluation of all mentioned facilities and programmes together with their schedule and expected quantitative results it is seen already, that only under the most favourable conditions one could decide by the mid to end '80s to build INTOR. International collaboration strongly increases the completeness of R+D required for INTOR.

C o n t e n t s

Introduction	p. 1
Contributions to INTOR related R+D	p. 2
Coverage of INTOR R+D demand	p. 2
Coverage of INTOR R+D demand until end of 1985	p. 4
Completeness of INTOR R+D	p. 4
Conclusions	p. 5
Classification of coverage for INTOR R+D	p. 5
Figure 1	p. 7
Figure 2	p. 8
Tables 1 - 5	
Enclosure 1	
References	

Introduction

Since 1978 under the auspices of IAEA the INTOR study concerning a next generation Tokamak (after JET - JT-60 - TFTR - T-15) is carried out with the participation of EURATOM, Japan, USA and USSR. After the conclusion of the data base assessment phase end of 1979 the definition phase was started. For these first two phases workshops have been organized in Vienna.

The contents of this report have been prepared for INTOR workshop sessions during the definition phase (Phase One).

In the frame of the international effort to define INTOR an assessment of the required R+D has been prepared (see International Tokamak Reactor Zero Phase Report, IAEA Vienna, 1980). Basing on this assessment during Phase One of the INTOR workshop a comparison was made between the anticipated INTOR design and construction schedule and the schedule of INTOR related R+D required before design freezing and/or start of fabrication.

In this comparison, which takes the form of bar charts for 16 different R+D topics with their pertaining subtopics, both an idealized R+D programme schematic and the actual timing of running and planned programmes are contained thus enabling a rather direct rough judgement on the coverage of INTOR related R+D requirements and on the possible time scale of INTOR realization. (For bar charts see Enclosure 1.)

The information collected in an iterative manner from all delegations to the INTOR workshop on running and planned programmes is qualitative so far in the sense that only indications have been given as to whether certain facilities or programmes can (or could) provide results pertaining to a certain subtopic at a certain time. Quantitative information like parameters to be achieved, cost involved for tackling additional questions in existion facilities, possibility to provide in practice all answers requested from certain facilities a.s.o. will have to be collected later as the INTOR work proceeds.

Despite this more qualitative character of the bar charts thus far, a rearrangement of the information permits some quantitative conclusions such

as on a possible overloading of certain facilities, lacking programme parts and coverage of the INTOR related R+D requirements in national or cooperative international programmes.

Contributions to INTOR related R+D

Table 1 shows a summary of all present entries (as of February 1981) in the INTOR bar charts (Enclosure 1). The R+D topics are regrouped in order to distinguish between plasma physics and technology, whereas the facilities besides of this aspect have been ordered roughly in chronological sequence according to their respective date of commissioning. This leads to the accumulation of data mainly in the left upper and right lower part of the Table. A few observations are the following:

- The solution of the open plasma physics questions bears on about ten tokamaks including the four large ones, which show by far the majority of entries. This calls for a careful review whether this would lead to overloading their programme in practice. Overloading of experiments due to a considerable number of technological contributions expected for INTOR may not be of comparable importance since these contributions are mostly results achieved in constructing and operating these machines.
- Roughly about 70% of the entries concerning technical topics mean expected results from plasma physics experimental programmes, whereas only about 30% of the entries refer to results expected from specialized technology test facilities.
- About 55% of the entries refer to open plasma physics questions, which underlines the necessity to make the most efficient use of the available machines in order to supply all necessary information in time for INTOR.

Coverage of INTOR R+D demand

From Table 1 it cannot be seen to what extent the subtopics under the different R+D topics are covered by the entries. Some subtopics are not

covered at all (see Table 2). It appears, however, that the effort needed to cover also those missing ones should not change the overall picture.

In order to estimate the existing coverage of INTOR related R+D demand one has to assume for the time being that the subtopics are items of equal importance. In a possible subsequent assessment subtopics covered just by one programme in one country may be weighted in a different manner as compared to other subtopics with many entries from several national programmes a.s.o. In the INTOR Zero Phase Report the R+D topics had been classified as adequately or inadequately covered. In the meantime further assessment and planning has changed the initial picture considerably which can be seen in the charts where the subtopics are still grouped in the sequence of the initial classification.

With a total number of 620 specific entries on R+D activities in INTOR participants' programmes (running, started, planned) the coverage of INTOR R+D demand has been evaluated in the following way. Assigning 100% coverage to the total R+D demand listed under the 16 topics and relating to this the percentage of subtopics actually covered by at least one entry the relative fulfillment of R+D requirements has been calculated for the four INTOR participants individually and for all possible combinations of two or three of them together with the case of all four cooperating.

The result is given in Table 4, in which also a classification of the degree of coverage is indicated. The classification into three categories of different relevance is explained on page 5.

In short this classification distinguishes between

coverage	100% - 67%	= relevant	= category I
	66% - 34%	= questionable relevance	= category II
	33% - 0%	= irrelevant for INTOR	= category III

The two lower categories are indicated in each column of Table 4. Assuming larger uncertainties about the R+D programmes found in the two lower categories the partner combinations can be mainly considered for their number of category I topics.

Coverage of INTOR R+D demand until end of 1985

The INTOR R+D bar charts in their present form infer from the anticipated INTOR design and construction schedule (see top part of each chart) that in an ideal R+D programme schematic all information should be available until end of 1985. Neglecting the inconsistency that the entries in the charts often refer only to data base assessment stages, leaving out decision making stages and their required time, and taking the optimistic view that - if information is indicated until end of 1985 - subtopics mentioned by at least one entry count for coverage one can set up a more stringent listing (see Table 5), in which all entries after end of 1985 are left out. This then characterizes the near term situation of INTOR related R+D.

Since there is hidden overlap sometimes in the subtopics a further Table 3 is added from which to see which participant contributes to which subtopic in the listings of Tables 4 and 5.

Completeness of INTOR R+D

Defining completeness as the percentage of R+D topics in category I one can set up the result of the present R+D assessment in a rather condensed form. Fig. 1 shows completeness of INTOR R+D versus all possible partner combinations and indicates the clear tendency to high completeness in multilateral cooperation. In addition the percentage of topics in category II is drawn up. Also the effects of restricting INTOR R+D to what could be expected until end of 1985 are to be seen.

It must be stated, however, that more conclusive results could only be expected from detailed assessments of quantitative R+D needs for INTOR and the possibility to quantitatively fulfill the needs by the times indicated. Insofar the present assessment cannot really judge whether INTOR R+D can be provided to a sufficient degree when called for by the anticipated schedule.

In order to illustrate the specific European situation with respect to INTOR related R+D Fig. 2 shows the completeness of R+D in the EURATOM

programme for the individual topics. The influence of specific results expected from some planned experiments is indicated assuming that their contribution will not greatly change the picture under topics with entries from existing facilities.

Conclusions

On the basis of existing information as of the INTOR bar charts (February 1981) one can derive the following conclusions:

- International collaboration strongly increases the completeness of R+D required for INTOR construction.
- For a further assessment of R+D related to INTOR it is important to collect more data and facts about the experiments and facilities listed and on the real possibility that they respond to all the INTOR demands to the required degree and by the time necessary.
- Also a more detailed planning network for INTOR design and construction is needed in order to check with a realistic R+D programme.
- Only under the most favourable conditions as
 - a) rapid implementation of supporting programmes
 - b) successful completion of all required R+D by the date indicated
 - c) very efficient international cooperationdoes it seem possible that in the mid to end '80s a decision to build INTOR could be taken.

Classification of coverage for INTOR R+D

The implementation time of any major facility from which R+D questions shall be answered for INTOR may be so long, that its present nonexistence means that INTOR could only be realized with considerable delay if it had to wait for construction of that facility. In a very general sense this holds similarly for important R+D programmes yet to be started. Therefore, as a crude indication for the coverage of any existing INTOR oriented R+D programme one can use the following definitions:


- 67% - 100% of necessary R+D existing, started, planned = relevant
- 34% - 66% of necessary R+D existing, started, planned = questionable relevance
- 0% - 33% of necessary R+D existing, started, planned = irrelevant for INTOR

Irrelevant as used here means that a sufficiently broad R+D programme could only be implemented with drastic programme changes and funding increase and considerable delay of INTOR realization. Questionable relevance means the same but to a lesser degree such that INTOR could in the end be realized with some tolerable delay. A relevant programme would be such that with some augmentation a decision to build INTOR could be taken in the mid to end '80s.

Fig. 1

R+D required for INTOR


Completeness of R+D for various partner combinations according to INTOR R+D bar charts as of February 1981



==== All expected results included (see Table 4)

----- Expected results until end of 1985 (see Table 5)

Fig. 2 Completeness of INTOR related R+D topics in the EURATOM programme



— All expected results included (see Table 3)

- - - - - unique results expected from planned experiments (as indicated) excluded

Table 1

R+D TOPICS		P L T	J A P - E X P S	P R I N G B O O G	T O M - 2 3	T M - 4 + F T - 1	T - 7	T - 1 1	T - 1 1	T - 1 3	T B - 0	F T	I S X - B	A L T E R - C	D I T R	P D X	D O U B L E T 3	A S D E X T O R	I S X - C	J E T T	J - 1 5	T O R E 2	J T P H Y R	U S P A - F C L T S	U S S R - F C L T S	I R E K	M I M S	N G I S - 1 5 0	K W R - 2 6 0	W R R - 2 6 0	S T M - 2	L S T F	2 O M J - C O I L	I N E N S F	H I N S F	V E T L + F N S	Nr. of entries /topic																	
P L A S M A	1. Energy and Particle Confinement	2	9	1	1	3	1	1	1	1	1	1	1	1	4	1	4	5	4	3	7	9	5	5	5																	83												
	3. Impurity Control, Fueling and Exhaust	2	8	1	1		1	3	2	2	1	7		4	1	7	3	7	3	6	3	2	4	4	1																	73												
	4A Heating - Neutral Beam																				5	2	1	10	6	3	1														28													
P H Y S I C S	4B Heating - RF	2	3			1	1	3			2	1		2	2	1	1			3	2	2	2	1	1																32													
	11. Stability Control	2	6	1	1	1		3	3	1		4	2	4	4	5	1	4	9	6	6	2	6	2																	73													
	12. Start-up, Burn and Shutdown Control	4	8			1	2	4	2			3	3	1	1	3	6	4	1	8	10	6	5	4																	76													
	Σ	12	34	1	2	2	1	3	4	1	6	8	2	3	4	2	5	3	1	1	5	2	9	2	1	10	8	3	1	-	-	-	-	-	-	-	-	-	-	365														
T E C H N O L O G Y	2. First Wall, Blanket and Shield														1		1				4	6	1	2	3												1	1		22														
	5. Magnetics		2			1							1	1	1	1	1	1	1	1	1	4	4	2			1	2							2	1				24														
	6. Materials						1						1		1		1				4	3	2		14		1		5	2						1				35														
	7. System Integration and Support Structure																																							-														
	8. Power Supply and Transfer																				6	6	8	7		2	1													30														
	9. Assembly and Remote Maintenance						1														3	3	1		2															10														
	10. Shielding and Personnel Access																											3		1							2			6														
	13. Tritium																				4	4	1	1					1						8		1	4		24														
	14. Vacuum					1	3	1	1							2	1	3			3	4	6	1		1	7	2						2	2	1				41														
	15. Safety and Environment							1													3	3	1					1	2	2	2				1	1	2			19														
	16. Diagnostics, Data Acquisition and Control			1		1		1													10	10	5	4		1														44														
	Σ	-	2	-	-	1	5	2	3	1	-	-	-	-	1	2	1	2	3	4	1	3	3	9	2	4	1	1	7	5	-	1	8	3	2	7	2	4	1	3	9	1	1	1	2	9	255							
	Number of entries per facility	12	36	1	2	4	1	4	9	18	11	3	3	4	2	5	3	1	2	7	1	2	4	1	3	8	1	8	6	7	3	5	4	8	3	9	1	6	10	2	11	4	2	7	2	4	13	9	1	1	1	2	9	620

) Entries not referring to a specific facility or program have not been taken into account.

JAP-Experiments: Doublet III (J), JFT-2, JFT-2M

USSR-Facilities: U-3, MIN II, IREK II, ISTR, RF-C, LUMSI, CYCL, WWR-M, IRT, ESU-VI, WWR-K, MAMONT, ILU-4, IWW-2M, TFC

USA-Facilities: METF, HPTF, NBETF

February 18, 1981/KÜ

INTOR R+D SUBTOPICS NOT COVERED SO FAR

- 4A Heating - Neutral Beam
 - Reliability and remote maintenance

- 4B Heating - RF
 - Vacuum windows resistant to thermal loading, neutron radiation and high RF power

- 2. First Wall, Blanket and Shield
 - Study of heat storage devices for smoothing out the power output

- 5. Magnetics
 - Divertor test stand

- 9. Assembly and Remote Maintenance
 - PF coil joints if required for internal coils

- 10. Shielding and Personnel Access
 - General shield design methods
 - Multi-dimensional transport techniques for streaming

- 13. Tritium
 - Resolve tritium shipping, accountability and safeguard issues
 - Study the influence of a divertor on the tritium system

- 15. Safety and Environment
 - Assess the consequences of earthquakes on the safe operation of INTOR
 - Exposure to electromagnetic radiation (guidelines)

Table 3

R+D CONTRIBUTIONS TO SUBTOPICS

1.	EUR	JAP	USA	USSR	3.	EUR	JAP	USA	USSR	4A	EUR	JAP	USA	USSR	4B	EUR	JAP	USA	USSR
- x	x	x	x	x	- x	x	x	x	x	- x	x)	x	x	- x	x	x	x	x	
- x	x	x	x	x	- x	x	x	x	x	- x	x	x	x	-	x	x	x	x	
- x	x	x	x	x	- x	x	x	x	x	- x	x)	x	x	-	
- x	x	x	x	x	- x	x	x	x	x	-	x)	x	x	- x	.	.	x	x	
- x)		x)			- x		x			- x	x)		x	-					
- x	x				-	x	x			- x				-					
- x)		x	x)		- x	x	x			-	.	.	.	-	
- x	x)	x	x)		-		x	x		-			x	-					

11.	EUR	JAP	USA	USSR	12.	EUR	JAP	USA	USSR	2.	EUR	JAP	USA	USSR	5.	EUR	JAP	USA	USSR
- x	x	x	x	x	- x	x	x	x	x	- x	x	x	x	- x	x	x	x	x	
- x	x	x	x	x	- x	x	x	x	x	-		x		- x					
- x	x	x	x	x	- x	x	x	x	x	-	.	.	.	- x	x	x	x	x	
- x	x	x	x	x	- x	x)	x			- x		x		- x	x			x	
- x	x	x	x	x	- x	x	x	x	x	- x	x			-	x	x	x	x	
- x)	x	x	x)		- x	x	x	x	x	- x)				-	x	x	x	x	
					- x)		x	x		-	x	x	x	-	

6.	EUR	JAP	USA	USSR	8.	EUR	JAP	USA	USSR	9.	EUR	JAP	USA	USSR	10.	EUR	JAP	USA	USSR
- x			x		- x	x	x	x	x	- x	x	x		-	x		x	x	
- x			x		- x	x	x	x	x	-	x			-	.	.	.	x	
-			x		-	x				- x		x		-	.	.	.	x	
- x)			x	x	- x	x	x	x	x	- x	x)	x		-	.	.	.	x	
- x			x		- x	x	x	x	x	-	.	.	.	-	x			x	
- x)			x							- x)	x)								
- x			x							-	.	.	.						
- x			x							- x)	x	x		- x	x	x	x	x	
- x			x							- x		x		- x)		x	x	x	
- x			x							-	.	.	.	- x		x	x	x	

13.	EUR	JAP	USA	USSR	14.	EUR	JAP	USA	USSR	15.	EUR	JAP	USA	USSR	16.	EUR	JAP	USA	USSR
-	x)	x	x		- x			x	x	- x	x)	x	x	- x	x)	x	x	x	
-	x)	x			- x		x	x		-		x)		- x	x	x	x	x	
-	x)	x			- x		x			-	x)	x)		- x	x	x	x	x	
- x	x	x	x		-	x	x	x		- x				- x	x	x	x	x	
- x)			x		-			x		- x)	x	x		- x	x	x	x	x	
- x)			x		-			x		- x		x		- x)		x	x	x	
-	.	.	.		- x	x	x	x	x	-	.	.	.	-	
-	.	.	x		-		x	x		-	.	.	.	-	
-	.	.	.		-		x			-	.	.	.	-	

1. Topic-Number (for characterization see Table 1)
- Subtopics (the number and sequence is the same as in the R+D bar charts as of Febr. 1981)
x Contributions until end of 1985
x) Contributions after 1985
. Subtopic not covered (see Table 2)

February 18, 1981 / Kü

Table 4

Coverage of INTOR Related R+D for Different Combinations of INTOR Partners

R+D TOPICS	Single				2 Partners				3 Partners				a11 %	
	JAP	USA	USSR		JAP+ USSR %	JAP+ USA %	EUR+ USA %	USA+ USSR %	EUR+ USSR %	EUR+ JAP+ USA	JAP+ USA+ USSR	EUR+ USA+ USSR		
	%	%	%	%	%	%	%	%	%	%	%	%		%
1. Energy and Particle Confinement	75	100	75		88	100	100	100	100	100	100	100	100	
3. Impurity Control, Fueling and Exhaust	63	100	63		88	100	100	100	88	100	100	100	100	
4A Heating - Neutral Beam	63	63	75		75	75	88	75	88	88	75	88	88	
4B Heating - RF	50	75	75		75	75	75	75	75	75	75	75	75	
11. Stability Control	100	100	100		100	100	100	100	100	100	100	100	100	
12. Start-up, Burn and Shutdown Control	86	100	86		100	100	100	100	100	100	100	100	100	
2. First Wall, Blanket and Shield	43	57	29		43	71	86	57	71	86	71	86	86	
5. Magnetics	63	63	50		75	88	88	75	75	88	75	88	88	
6. Materials	80	40	100		100	80	90	100	100	90	100	100	100	
8. Power Supply and Transfer	80	80	80		100	100	80	80	80	100	100	80	100	
9. Assembly and Remote Maintenance	57	43	14		71	71	57	57	71	86	86	71	86	
10. Shielding and Personnel Access	0	0	60		60	40	0	60	60	40	60	60	60	
13. Tritium	30	70	30		50	80	70	80	50	80	70	80	80	
14. Vacuum	50	60	80		80	60	80	100	90	80	100	100	100	
15. Safety and Environment	44	44	33		56	44	56	67	67	56	67	78	78	
16. Diagnostics, Data Acq. and Control	86	100	100		100	86	100	100	100	100	100	100	100	

) Topic 7 being not really a R+D subject has been omitted in this table

0 - 33% = irrelevant for INTOR (category III)
 34 - 66% = questionable relevance (category II)
 67 - 100% = sufficient, relevant (category I)

R+D TOPICS	Single				2 Partners						3 Partners				all %
	EUR %	JAP %	USA %	USSR %	JAP+USSR %	JAP+USA %	EUR+JAP %	EUR+USA %	USA+USSR %	EUR+USSR %	EUR+JAP+USA %	JAP+USA+USSR %	EUR+JAP+USSR %	EUR+USA+USSR %	
1. Energy and Particle Confinement	75	63	88	50	63	88	75	88	88	75	88	88	88	88	
3. Impurity Control, Fueling and Exhaust	75	63	100	63	88	100	88	100	100	88	100	100	100	100	
4A Heating - Neutral Beam	63	13	63	75	75	63	63	88	75	88	75	88	88	88	
4B Heating - RF	50	50	75	75	75	75	75	75	75	75	75	75	75	75	
11. Stability Control	83	100	100	83	100	100	100	100	100	100	100	100	100	100	
12. Start-up, Burn and Shutdown Control	86	71	100	86	100	100	86	100	100	100	100	100	100	100	
2. First Wall, Blanket and Shield	43	43	57	29	43	71	57	71	57	71	57	71	71	71	
5. Magnetics	63	75	63	50	75	75	88	88	75	88	75	88	88	88	
6. Materials	60	0	40	100	100	40	60	90	100	60	100	100	100	100	
8. Power Supply and Transfer	80	100	80	80	100	100	100	80	80	100	100	100	80	100	
9. Assembly and Remote Maintenance	43	29	43	14	43	57	57	43	57	57	71	71	57	71	
10. Shielding and Personnel Access	0	40	0	60	60	40	40	0	60	40	60	60	40	60	
13. Tritium	10	10	70	30	30	70	10	70	30	70	80	30	80	80	
14. Vacuum	50	20	60	80	80	60	60	80	100	80	100	90	100	100	
15. Safety and Environment	33	11	33	33	44	33	44	44	56	44	56	56	67	67	
16. Diagnostics, Data Acq. and Control	71	43	100	86	86	100	71	100	100	100	100	86	100	100	

) Topic 7 being not really a R+D subject has been omitted in this table

□ 0 - 33% = irrelevant for INTOR (category III)

○ 34 - 66% = questionable relevance (category II)

67 - 100% = sufficient, relevant (category I)

I N T O R · R + D B A R C H A R T S

including comments from all delegations during
INTOR workshop phase I (March 1980-Febr. 1981)

compiled by A. Knobloch

Comments to bar charts

In a conventional undertaking bar charts are the results of a planning network which includes all cross links and interdependencies between items included. For INTOR at the present state R+D bar charts can only give a very first overview on the situation. Thus a considerable degree of inconsistency will have to be resolved yet.

For the present version of bar charts a separation between the bar charts concerning R+D for INTOR (with its data base assessment and decision making stages) and the stages of relevant experiments and R+D programs has been made, the latter being indicated on transparent sheets. This offers the possibility to

- discuss separately the appropriate R+D program plan in accordance with the realization stages of the INTOR project as worked out during the workshop sessions, and the overall situation of the INTOR relevant R+D programs;
- get an indication on a proper and realistic timing of the INTOR project.

During the discussions it became clear that a number of further steps have to be taken in order to make the R+D bar charts a useful tool. These include:

- Improvement of the R+D definitions
- Getting more details on expected results from experiments and programs and on their status of approval
- Evaluation of required results from R+D according to INTOR design and construction schedule
- Discussion of consequences for INTOR definition and planning

Procedure followed in present bar chart version

- In order to give an indication for the realization stages of the INTOR project, the general definitions from the March 1980 versions together with the INTOR schedule as of the INTOR workshop were used. It was felt practical to show the assumed duration and overlap of the phases of INTOR realization since this eases the discussion of the principal R+D bar charts and their future extrapolation for the needs of later stages of INTOR operation which are not included so far. Also the implications for decision making become more clear.
- The entries concerning stages of experiments and R+D programs at which certain degrees of data base assessment are expected from them have been optimistically made one year after the pertinent scheduled start of operation. Multiple appearance of the same experiment or program means consecutive achievement of relevant portions of information. Especially the underlined entries refer to operation with tritium.

BAR CHART - INTOR R+D DESIGNATIONS

1. Realization stages of the project

- D - Conceptual design
- E - Engineering design
- P - Production design
- C - Construction, equipment fabrication
- A - Assembly
- T - Testing
- O - Operation

2. Decision-making stages


- MS - Concept selection
- CS - Final version selection, final check

3. Data base assessment stages

- I - Information collection
- F - Feasibility justification
- P - Prototype construction
- FP - Full power testing


1. ENERGY and PARTICLE CONFINEMENT

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
INTOR schedule:													
conceptual design													
engineering design													
production design													
fabrication, construction													
assembly													
engineering tests													



2. FIRST WALL, BLANKET and SHIELD

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
<p>Year</p> <p>1980</p> <p>1981</p> <p>1982</p> <p>1983</p> <p>1984</p> <p>1985</p> <p>1986</p> <p>1987</p> <p>1988</p> <p>1989</p> <p>1990</p> <p>1991</p> <p>1992</p>													
<p>INTOR schedule: conceptual design engineering design production design fabrication, construction assembly engineering tests</p>													
<p>((PRD Adequate))</p> <ul style="list-style-type: none"> -- Determination of heat flux limits under normal operation for first wall and limiter materials, theoretical and experimental -- Out of reactor tests of standard blanket, shield and first wall components and mockups (thermal hydraulics, pressure and thermal load response) -- Study of heat storage devices for smoothing out the power output 													
<p>((PRD Inadequate))</p> <ul style="list-style-type: none"> -- Development of methods to protect the first wall against plasma disruption (e.g. limiters or mechanical devices) -- Determination of heat flux limits for limiters, divertor dumps and targets -- Clarification of the needs and operating conditions of electrically insulating parts in the first wall and shield region -- Neutronic study, including computer codes and integral experiments 													




2. FIRST WALL, BLANKET and SHIELD

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
INTOR schedule: conceptual design engineering design production design fabrication, construction assembly engineering tests													
(R+D Adequate)													
- Determination of heat flux limits under normal operation for first wall and liner materials, theoretical and experimental													
- Out of reactor tests of standard blanket, shield and first wall components and mockups (thermal hydraulics, pressure and thermal load response)													
- Study of heat storage devices for smoothing out the power output													
(R+D Inadequate)													
- Development of methods to protect the first wall against plasma disruption (e.g. liners or mechanical devices)													
- Determination of heat flux limits for limiters, divertor dumps and targets													
- Clarification of the needs and operating conditions of electrically insulating parts in the first wall and shield region													
- Neutronic study, including computer codes and integral experiments													


(R+D Adequate)

(R+D Inadequate)




3. IMPURITY CONTROL, FUELING and EXHAUST

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
INTOR schedule:													
conceptual design engineering design production design fabrication, construction assembly engineering tests													
((R+D Adequate))													
- Experimental data on plasma-wall interactions and edge plasma control in discharges with and without a divertor, in the presence of strong auxiliary heating	JFT-2 PETULA T-11	PLT POX T-11	Doublet E ISX-B TFTR TF-10	JFT-2H	TFTR	U-3 T-10 T-15 JET	TFTR						
- Experimental and theoretical studies of physical processes in: - poloidal divertors	D-III(D)DEX AS-DEX ISX-B RIS	Doublet E PDX	MS	JFT-2H	JFT-2H	TB-0 ISX-C	JFT-2H						
- Experimental studies of pellet injection both in ohmically heated plasmas and in the presence of strong auxiliary heating	ISX-B RIS PDX	ASDEX RIS	ASDEX, DITE ISX-B PDX	T-10									
- Surface physics studies of impurity generation and particle recycling processes	DITE JFT-2	ASDEX ISX-B	T-7 T-11	JFT-2H	PDX ASDEX DITE TEXTOR	TFTR JET							
((R+D Inadequate))													
- Experimental and theoretical studies of physical processes in: - local, e.g. bundle, divertors	D-III(C)	PDX	DITE			ISX-C							
- Design studies of divertors suitable for INTOR	JFT-2	ASDEX RINGROOGE PDX TEXTOR	MS ASDEX ISX-B										
- Experimental study of non-divertor techniques for ash exhaust and impurity removal													
- Technology of D and T pellet injection at the required high repetition rate, at a minimum speed of 10 ³ m/sec, with a design goal of 5 x 10 ³ m/sec													




3. IMPURITY CONTROL, FUELING and EXHAUST

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
INTOR schedule:	conceptual design engineering design production design fabrication, construction assembly engineering tests												
(R+D Adequate)	<ul style="list-style-type: none"> - Experimental data on plasma-wall interactions and edge plasma control in discharges with and without a divertor, in the presence of strong auxiliary heating - Experimental and theoretical studies of physical processes in: <ul style="list-style-type: none"> • poloidal divertors - Experimental studies of pellet injection both in ohmically heated plasmas and in the presence of strong auxiliary heating - Surface physics studies of impurity generation and particle recycling processes 												
(R+D Inadequate)	<ul style="list-style-type: none"> - Experimental and theoretical studies of physical processes in: <ul style="list-style-type: none"> • local, e.g. bundle, divertors - Design studies of divertors suitable for INTOR - Experimental study of non-divertor techniques for ash exhaust and impurity removal - Technology of D and T pellet injection at the required high repetition rate, at a minimum speed of 10³ m/sec, with a design goal of 5 x 10³ m/sec 												




4A. HEATING - NEUTRAL BEAM

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
INTOR schedule: conceptual design engineering design production design fabrication, construction assembly engineering tests													
-- Heating (NB and/or RF)													
(R+D Adequate)													
- Ion Beam. Development of high-current (~100 A) ion beam at 175 keV (preferably 200 keV if practicable)													
- Pulse length. Development of a 10 s pulse capability for the ion source and the beam dump, which must handle 0.5 MW/cm ² with direct recovery and ~2 MW/cm ² without direct recovery. In addition, certain of the units should have a 100 s capability													
- Monatomic Fraction. A 90% D ⁺ fraction in the ion beam should be a design goal, with 80% a minimum requirement													
(R+D Inadequate)													
- Direct Recovery. Development of a direct recovery system for the unneutralized beam ions with at least 60% efficiency is almost certainly required													
- Efficiency. Simultaneous achievement of high neutralization efficiency, high transmission efficiency, long ducts and low gas flow to the plasma													
- Radiation Hardening. Adequate lifetime of all injector components against the expected neutron bombardment and other radiation must be insured. A plug valve should be developed for insertion in the beam ducts at the end of the heating pulse													
- Reliability and Remote Maintenance. - Negative ion beams													




4A. HEATING - NEUTRAL BEAM

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
INTOR schedule: conceptual design engineering design production design fabrication, construction assembly engineering tests													
- Heating (NB and/or RF)		I	MS	MS	MS	MS	MS	MS	MS	MS	MS	MS	MS
(R+D Adequate)													
- Ion Beam. Development of high-current (~100 A) ion beam at 175 keV (preferably 200 keV if practicable)													
- Pulse Length. Development of a 10 s pulse capability for the ion source and the beam dump, which must handle ~0.5 kW/cm ² with direct recovery and ~2 kW/cm ² without direct recovery. In addition, certain of the units should have a 100 s capability													
- Monatomic Fraction. A 90% D ⁺ fraction in the ion beam should be a design goal, with 80% a minimum requirement													
(R+D Inadequate)													
- Direct Recovery. Development of a direct recovery system for the unneutralized beam ions with at least 60% efficiency is almost certainly required													
- Efficiency. Simultaneous achievement of high neutralization efficiency, high transmission efficiency, long ducts and low gas flow to the plasma													
- Radiation Hardening. Adequate lifetime of all injector components against the expected neutron bombardment and other radiation must be insured. A plug valve shield should be developed for insertion in the beam ducts at the end of the heating pulse													
- Reliability and Remote Maintenance. - Negative ion beams													




4B. HEATING - RF

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
INTOR schedule:													
conceptual design													
engineering design													
production design													
fabrication, construction													
assembly													
engineering tests													
- Heating (NB and/or RF)													
(R+D Adequate)													
- MW-level experiments to prove heating effectiveness, followed by demonstrations of heating larger plasmas to reactor temperatures (ICRF. LHH)													
- Experimental verification of absorption and heating by ECH at the 200-400 kW level, followed by MW level experiments													
(R+D Inadequate)													
- Vacuum windows resistant to thermal loading, neutron radiation and high RF power													
(R+D Inadequate, New Facility Required)													
- ICRF and LHH launching structures resistant to thermal loading and neutron radiation													




5. MAGNETICS

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
<p>INTOR schedule: conceptual design engineering design production design fabrication, construction assembly engineering tests</p>													
<p>((R+D Adequate))</p> <ul style="list-style-type: none"> -- Superconducting toroidal coil development and 1/2 tesla (Nb₃Sn) conductor development -- 111 tesla NbTi super fluid Helium cooling -- Superconducting magnetic systems integration experience -- Development of large, reliable cryogenic systems 													
<p>((R+D Inadequate))</p> <ul style="list-style-type: none"> -- Superconducting induction coil development -- Internal poloidal field coil development, if required <p>((R+D Inadequate, New Facility Required))</p> <ul style="list-style-type: none"> -- Divertor development -- Divertor test stand 													




5. MAGNETICS

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
INTOR schedule:													
conceptual design													
engineering design													
production design													
fabrication, construction													
assembly													
engineering tests													
(R+D Adequate)													
- Superconducting toroidal coil development and 12 tesla (Nb ₃ Sn) conductor development													
- 11 tesla NbTi super fluid Helium - cooling													
- Superconducting magnetic systems integration experience													
- Development of large, reliable cryogenic systems													
(R+D Inadequate)													
- Superconducting induction coil development													
- Internal poloidal field coil development, if required													
(R+D Inadequate, New Facility Required)													
- Divertor development													
- Divertor test stand													




6. MATERIALS

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
INTOR schedule:													
conceptual design													
engineering design													
production design													
fabrication, construction													
assembly													
engineering tests													
(R+D Adequate)													
- Generation of irradiation effects data (e.g. mechanical properties) on nickel containing alloys for design purposes													
- Environmental effects on fatigue of SS at elevated temp. incl. irradiation													
- Determine synergistic effects of stress/strain and irradiation on key properties of stabilizer materials													
- Generation of irradiation effects data on superconductor and insulator materials as required for engineering design													
- Determine chemical erosion characteristics of materials and coatings exposed to plasma at high temperature and high fluence conditions													
- Determine chemical and radiation stability of breeding materials under irradiation at elevated temperatures and chemical reactivity with structures and/or coolant													
(R+D Inadequate)													
- Development of fabrication techniques and data base on bulk irradiation effects for non-stainless steel structural materials and non-structural first-wall or liner materials (ceramics, graphite, insulators)													
- Develop retention/release characteristics of T and He on materials exposed to plasma (first-wall, liners, limiters, divertor collectors) under design conditions													
- Development of low-Z coatings for first-wall or liner components (fabrication, irradiation effects and thermal shock resistance)													
- Study the effect of gaseous transmutants on mechanical properties of structural materials which do not contain Ni													




88. POWER SUPPLY and TRANSFER

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
<p>INTOR schedule:</p> <ul style="list-style-type: none"> conceptual design engineering design production design fabrication, construction assembly engineering tests 													
<p>(READ ADEQUATE)</p> <ul style="list-style-type: none"> Energy storage flywheel generators superconducting storage systems 													
<ul style="list-style-type: none"> Switches MV switch tubes vacuum circuit breakers SCR switches 													
<ul style="list-style-type: none"> Thyrt. conv. reactive power comp. Neutral beam injection transmission lines ion source protection neutral beam power supplies radio frequency system cryostats system development at 120150 GHz, 5500 kW, 5 s pulse LCRF, LHH power supplies 													



9. ASSEMBLY and REMOTE MAINTENANCE

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
<p>INTOR schedule: conceptual design engineering design production design fabrication, construction assembly engineering tests</p>													
<p>(R+D Adequate)</p> <ul style="list-style-type: none"> - General remote handling apparatus - Develop reactor mockup - Develop remote welding and cutting systems 													
<p>(R+D Inadequate)</p> <ul style="list-style-type: none"> - Develop viewing and inspection systems for remote welding - Methods for failure rate analysis and verification of components - PF coil joints if required for internal coils - Optimized engineering function suited for remote maintenance 													



9. ASSEMBLY and REMOTE MAINTENANCE


Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
INTOR schedule:													
conceptual design													
engineering design													
production design													
fabrication, construction													
assembly													
engineering tests													
(R+D Adequate)													
- General remote handling apparatus													
- Develop reactor mockup													
- Develop remote welding and cutting systems													
(R+D Inadequate)													
- Develop viewing and inspection systems for remote welding													
- Methods for failure rate analysis and verification of components													
- PF coil joints if required for internal coils													
- Optimized engineering function suited for remote maintenance													

(R+D Adequate)

- General remote handling apparatus
- Develop reactor mockup
- Develop remote welding and cutting systems


(R+D Inadequate)

- Develop viewing and inspection systems for remote welding
- Methods for failure rate analysis and verification of components
- PF coil joints if required for internal coils
- Optimized engineering function suited for remote maintenance



10. SHIELDING and PERSONNEL ACCESS

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
ANTOR schedule:													
conceptual design engineering design production design fabrication, construction assembly engineering tests													
(R+D Adequate)													
- Integral experiments for bulk shield													
- General shield design methods													
- Nuclear data for shielding													
(R+D Inadequate)													
- Multi-dimensional transport techniques for streaming													
(R+D Inadequate, New Facility Required)													
- Integral experiments for penetrations													



10. SHIELDING and PERSONNEL ACCESS

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
INTOR schedule: conceptual design engineering design production design fabrication, construction assembly engineering tests													
(R+D Adequate)													
- Integral experiments for bulk shield - General shield design methods - Nuclear data for shielding													
(R+D Inadequate)													
- Multi-dimensional transport techniques for streaming													
(R+D Inadequate, New Facility Required)													
- Integral experiments for penetrations													

(R+D Adequate)


- Integral experiments for bulk shield
- General shield design methods
- Nuclear data for shielding

(R+D Inadequate)

- Multi-dimensional transport techniques for streaming

(R+D Inadequate, New Facility Required)

- Integral experiments for penetrations




12. START-UP, BURN and SHUTDOWN CONTROL

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
Year													
INTOR schedule:	conceptual design engineering design production design fabrication, construction assembly engineering tests												
(R+D Adequate)	<ul style="list-style-type: none"> - Ionization and current rise at low loop voltage - Optimum current-rise scenario (experiments in large, in particular non-circular tokamaks) - Maximum density in clean ohmic discharges - Density rise and profile control during heating to ignition - Compatibility of heating schemes (neutral beam, RF or mixed) with parameter variation during heating to ignition - Smooth shut-down, in particular after intense heating 												
(R+D Inadequate)	<ul style="list-style-type: none"> - Burn temperature control, including diagnostics 												


113. TRITIUM

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
<p>ANTOR schedule: conceptual design engineering design production design fabrication, construction assembly engineering tests</p>													
<p>(R+D Adequate)</p> <ul style="list-style-type: none"> - Demonstrate performance, reliability and maintainability of integrated fuel handling system. Demonstrate performance of auxiliary safety (clean-up and backup) systems and tritium monitoring instrumentation (TSTA, TETL, VTS) - Study dynamics of enclosure clean-up operations following tritium spills - Develop and demonstrate removal of tritium from the coolant - Develop and demonstrate extraction of tritium from breeder materials 													
<p>(R+D Inadequate)</p> <ul style="list-style-type: none"> - Determine concentration and chemical composition of impurities exhausted from the plasma - Characterize tritium interaction with materials under realistic conditions - Develop effective barriers to tritium permeation - Resolve tritium shipping, accountability, and safeguard issues - Study tritium aspects of fuel fabrication and injection - Study the influence of a divertor on the tritium system 													



IV. VACUUM

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
<p>ANTOR schedule: conceptual design engineering design production design fabrication, construction assembly engineering tests</p>													
<p>((R+D Adequate))</p> <ul style="list-style-type: none"> - Development of baking, degassing, and discharge cleaning methods for stainless steel surfaces inside the vacuum vessel - Evaluation of radiation heating in cryopumps for NBI and development of alternate pumping techniques - Testing of vacuum seals suitable for remote disassembly and maintenance 													
<p>((R+D Inadequate))</p> <ul style="list-style-type: none"> - Development of high speed helium pumps - Development and testing of large dry turbomolecular pumps - Test of the performance of cryopumps in the presence of high neutron and gamma fluxes - Development of baking, degassing and discharge cleaning methods for Al alloys surfaces inside the vacuum vessel - Remote leak detection - Design and fabrication of large cryosorption pumps and confirmation of their performance - Development of vacuum components with large cross section (≥ 1 m²) 													



14. VACUUM


Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
INTOR schedule:	conceptual design engineering design production design fabrication, construction assembly engineering tests												
(R+D Adequate)	<ul style="list-style-type: none"> - Development of baking, degassing, and discharge cleaning methods for stainless steel surfaces inside the vacuum vessel - Evaluation of radiation heating in cryopumps for NBI and development of alternate pumping techniques - Testing of vacuum seals suitable for remote disassembly and maintenance 												
(R+D Inadequate)	<ul style="list-style-type: none"> - Development of high speed helium pumps - Development and testing of large dry turbomolecular pumps - Test of the performance of cryopanelts in the presence of high neutron and gamma fluxes - Development of baking, degassing and discharge cleaning methods for Al alloys surfaces inside the vacuum vessel - Remote leak detection - Design and fabrication of large cryosorption pumps and confirmation of their performance - Development of vacuum components with large cross section ($\geq 1 \text{ m}^2$) 												

(R+D Adequate)

- Development of baking, degassing, and discharge cleaning methods for stainless steel surfaces inside the vacuum vessel
- Evaluation of radiation heating in cryopumps for NBI and development of alternate pumping techniques
- Testing of vacuum seals suitable for remote disassembly and maintenance


(R+D Inadequate)

- Development of high speed helium pumps
- Development and testing of large dry turbomolecular pumps
- Test of the performance of cryopanelts in the presence of high neutron and gamma fluxes
- Development of baking, degassing and discharge cleaning methods for Al alloys surfaces inside the vacuum vessel
- Remote leak detection
- Design and fabrication of large cryosorption pumps and confirmation of their performance
- Development of vacuum components with large cross section ($\geq 1 \text{ m}^2$)



15. SAFETY and ENVIRONMENT

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
INTOR schedule: conceptual design engineering design production design fabrication, construction assembly engineering tests													
(R+D Adequate)													
- Develop reliable tritium handling, processing, containment and cleanup systems													
- Obtain activation product generation, release, transport and shielding data													
- Determine tritium conversion rates and biological effects													
- Obtain lithium and lithium compound fire consequences, prevention, extinguishment data													
(R+D Inadequate)													
- Develop probabilistic and mechanistic accident analysis techniques													
- Develop definitive magnetic field exposure guidelines for humans													
- Assess the consequences of earthquakes on the safe operation of INTOR													
- Exposure to electromagnetic radiation (guidelines)													
(R+D Inadequate, New Facility Required)													
= Obtain magnet accident experimental data													



T-15
(F)

15. SAFETY and ENVIRONMENT

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
INTOR schedule: conceptual design engineering design production design fabrication, construction assembly engineering tests													
(R+D Adequate)													
- Develop reliable tritium handling, processing, containment and cleanup systems													
- Obtain activation product generation, release, transport and shielding data													
- Determine tritium conversion rates and biological effects													
- Obtain lithium and lithium compound fire consequences, prevention, extinguishment data													
(R+D Inadequate)													
- Develop probabilistic and mechanistic accident analysis techniques													
- Develop definitive magnetic field exposure guidelines for humans													
- Assess the consequences of earthquakes on the safe operation of INTOR													
- Exposure to electromagnetic radiation (guidelines)													
(R+D Inadequate, New Facility Required)													
- Obtain magnet accident experimental data													


(R+D Adequate)

(R+D Inadequate)

(R+D Inadequate, New Facility Required)

16. DIAGNOSTICS, DATA ACQUISITION and CONTROL

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
INTOR schedule: conceptual design engineering design production design fabrication, construction assembly engineering tests													



16. DIAGNOSTICS, DATA ACQUISITION and CONTROL

Year	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992
INTOR schedule: conceptual design engineering design production design fabrication, construction assembly engineering tests													
<u>(R+D Adequate)</u>													
- High-β control, density and α-particle plasma diagnostics			I		F	CS							
- Blanket nuclear measurement technique			I		P	CS							
- Feedback control computer algorithms			I			CS							
- Reliability evaluation of control systems			I										
<u>(R+D Inadequate)</u>													
- Transient noise and damage measurements of detectors and transducers			I			CS							
- Radiation damage and thermal studies of optics system, vacuum seals and isolator materials			I		F	CS							
- First wall and blanket instrumentation techniques in tokamak environment			I			CS							

Facility/Program	Abbreviation	Location	Operational
	JET	Culham	12-1982
<u>Large Tokamaks:</u>	TFTR	Princeton	12-1981
	JT-60	JAERI	10-1984
	T-15	Moscow	12-1983
Tritium test facilities:	TSTA	Los Alamos	1981
	TETL	Japan	mid 80s
	VTS	USSR	mid 80s
Material test facility	FMIT	Hanford	authorized 1980
Neutron source	HINSF	Livermore	1980
Safety analysis	INEL	Idaho	1980
Poloidal coil test	20 MJ-coil	Los Alamos	fabrication 1980
Toroidal coil test	LCTF	Oak Ridge	1982
Vacuum test facility	KRIS	Moscow	
Medium energy beam test fac.	METF	Oak Ridge	yes
Ion source and neutral injection test facility	IREF	Moscow	
High power beam test fac.	HPTF	Oak Ridge	yes
Neg. ion source test fac.	MIN	Moscow	
Neutral beam engineering test facility	NBETF	Berkeley	1984
SC magnet test stand	SIMS	Moscow	
Water cooled research reacts.	WWR-2 + IWW-2M	"	
Neutron generator	NG-150	"	
1 MeV heavy ion accelerator	ILU-4	"	
Fast research reactor	BOR-60	Dimitrovgrad	
Water cooled research react.	SM-2	"	
Test facility for cryo-panels studies	TFC	Leningrad	
Research reactor	MR	Moscow	
Research reactor	WWR-M	Kiev	
Research reactor	MIR	Dimitrovgrad	
Research reactor	IRT	Salaspils/Riga	
Research reactor	WWR-K	Alma-Ata	
RF-complex	RF-C	Kiev	
10 MeV heavy ion accelerator	ESUVI	Kiev	
Mass-monochromator	Mamont	Moscow	
2-4 MeV helium, hydrogen ions accelerators	VG-4 LUMSI	Kiev	
Cyclotron	Cycl	USSR	
Torsatron for plasma RF-heating studies	U-3	Kiev	
Ion sources and energy recup.	ISTRA	USSR	
Fast neutron source	FNS	JAERI	

Facility/Programm	Abbreviation	Location	Operational
<u>Present Tokamaks and Tokamaks under construction:</u>			
	Doublet III (US/JAP. Coop.)	San Diego	yes
	PLT	Princeton	"
	PDX	Princeton	"
	ISX-B	Oak Ridge	"
	Alcator-A	Cambridge	"
	Alcator-C	Cambridge	"
	JFT-2	Tokai-mura	"
	Tuman-3	Leningrad	"
	TO-2	Moscow	"
	TM-3	Moscow	"
	TM-4	Moscow	"
	T - 7	Moscow	"
	T - 10	Moscow	"
	T - 11	Moscow	"
	T - 13	Moscow	"
	FT-1	Leningrad	"
	R-05	Sukhumi	"
	ASDEX	Garching	"
	TEXTOR	Jülich	1982
	TFR	Fontenay-aux-Roses	yes
	DITE	Culham	"
	FT	Frascati	"
	Petula	Grenoble	"
	WEGA	Grenoble	"
	Ringboog/SPICA	Jutphaas	"
<u>Planned Tokamaks:</u>			
	TORE II	France	
	ISX-C	Oak Ridge	
	Doublet III Large Dee	San Diego	2-1984 or 6-1985
	TB-0	USSR	
	ZEPHYR	Garching	
<u>Planned test facilities:</u>			
	IREK II	USSR	
	MIN II	USSR	

References

'INTOR R+D Programme Bar Charts' 2nd Meeting of the INTOR Workshop, USSR-Contributions, IAEA-Vienna, March 1980, unpublished

A.F. Knobloch: 'INTOR R+D Bar Charts' 3rd Meeting of the INTOR Workshop, European Contributions, IAEA-Vienna, June 1980, EUR FU BRU/XII 501/80/EDV 40

A.F. Knobloch: 'INTOR Related R+D' 4th Meeting of the INTOR Workshop, European Contributions, IAEA-Vienna, October 1980, EUR FU BRU/XII 501/80/EDV 60

A.F. Knobloch: 'INTOR R+D Bar Charts Partial Revision and Evaluation' 5th Meeting of the INTOR Workshop, European Contributions, IAEA-Vienna, January 1981, EUR FU BRU/XII 2/81/EDV 10

'U.S.A. R+D Program' 5th Meeting of the INTOR Workshop, USA-Contributions, IAEA-Vienna, January 1981, EUR FU BRU/XII 2/81/EDV 12

K.B. Kartashev, B.N. Kolbasov, V.N. Kursakov, E.B. Sergeev: 'INTOR R+D Programme Bar Charts' 5th Meeting of the INTOR Workshop, USSR-Contributions, IAEA-Vienna, January 1981, EUR FU BRU/XII 2/81/EDV 13