




Lessons learned in the construction of Wendelstein 7-X

Hans-Stephan Bosch
for the Wendelstein 7-X Team

Max-Planck-Institute for Plasma Physics, Greifswald, Germany




- Introduction
- Organisation of a big project - lessons learned
- Planning aspects - lessons learned
- Fabrication of components - lessons learned
- Integration - lessons learned
- Conclusions



major radius	5,5 m
minor radius	0,53 m
plasma volume	30 m ³
magnetic field	< 3 T
rot. transform	5/6 – 5/4
non-planar coils	50
planar coils	20

heating power	15 – 30 MW
pulse length	30 min
stored energy	600 MJ

device diameter	16 m
device height	4,5 m
device mass	725 t
cold mass	425 t



1991	EURATOM approval phase 1	1999	planned completion date
1995	EURATOM approval phase 2	2004	
1996	official project start	2006	
2000	inauguration of new building		
2002	insolvency Babcock GmbH (coil manufacturer) external audits of the project	2010	
2003	first restructuring of the project		
2004	device assembly interrupted due to coil repair second restructuring of the project	2012	
2005	assembly resumed third restructuring of the project		
2006	assembly plan revision counter measure package implemented	2016 2014	
2007	first magnet module completed		
2009	all magnets manufactured and tested assembly of four magnet modules in progress		
2011	all magnet modules assembled	2014	

- Introduction
- **Organisation of a big project** - lessons learned
- Planning aspects - lessons learned
- Fabrication of components - lessons learned
- Integration - lessons learned
- Conclusions

Organisation

- Clear responsibilities and structures are mandatory
- Structures are living and should be adapted to the phase of a project
- quick decision making must be secured
- Processes have to be reviewed and adapted regularly

But: Often not compatible with the institutional reality

Strong project planning and coordination

- a professional full-time team is required
- this team must have a lead function in the project

But: planning basis is often weak, man power not available


Appropriate infrastructure/tools for the project

- QMS (ISO 9001) which defines/monitors the processes within the project
- (Electronic) documentation of documents and CAD-models
- Clear boundary conditions should be defined also for the technical level (Handbooks, guidelines e.g. for materials, electronic or IT standards)


But: acceptance on the working level (scientists); “additional” effort


Evolution of project structure

1/2004



6/2011





- Introduction
- Organisation of a big project - lessons learned
- **Planning aspects** - **lessons learned**
- Fabrication of components - lessons learned
- Integration - lessons learned
- Conclusions

Realistic planning of time, budget and staff

- typically the estimates are too low \Rightarrow continuous increases
- cost increases and delays damage the relation to funding agencies and to the public

But: estimates usually are fixed in an early stage: planning not yet detailed enough, little man power

Contingencies are necessary


- a reasonable contingency avoids permanent revision of the planning
- without contingency, decision-making (work processes) are slowed down


But: in many cases, a contingency is not granted

Appropriate planning and monitoring tools

- standard tools of PM must be available from the beginning (PMP, WBS (multi-level), Milestones with trend analyses)
- detailed planning of work and finances (integrated planning)
- Earned Value Management

But: acceptance on the working level has to be enforced





reporting



Management Information System = MIS
used by project coordination, controlling, board, supervisors

check + report




check + release II



check + release I



planning work/costs



connector
reading and processing data

accounting



- Introduction
- Organisation of a big project - lessons learned
- Planning aspects - lessons learned
- **Fabrication of components** - **lessons learned**
- Integration - lessons learned
- Conclusions

Component design

- Design has to be completed (and checked) before tendering
- Design changes during the manufacturing have to be avoided
- clear specifications have to be provided

But: High time pressure and requirements on the fund flow

Fabrication skills and capacities

- Industry should have proven the skills and know-how
- Manufacturing capacities have to be secured
- complex consortia can be problematic - clear responsibilities preferred

But: Monopoly situation and competition with other fabrication priorities

Technical risks during development and fabrication

- Transfer of risk to industry is extremely expensive
- Risks should be minimized by in-house development


But: High work-load in-house \Leftrightarrow large, competent team required

Prototypes, tests and quality assurance

- Prototypes should be built when possible and affordable
- Tests of prototypes and series products is mandatory
- QA to be performed by the project team and by external inspectors

But: see above

W7-X coils – an European consortium



changes

- 1. cast steel casing instead of welded coil casing**
- 2. reinforcement of coil connection blocks***
- 3. reinforcement of planar coil casings***

* after revised structural calculations done at IPP

issues

- 1. deviations and damages of SC strands**
- 2. voids in cast steel coil casings**
- 3. geometrical deviations in coil casings**
- 4. residuals of Cu-SS soldering flux**
- 5. Al and SS welds to be requalified**
- 6. quench detection cable damage**
- 7. insulation faults in the coil header**
- 8. danger of shorts in the coil header**



Insulation tests

- 13 kV in vacuum, RT and 4K
- also under Paschen-conditions
- current monitoring
- camera observation of coil header

Complex & risky repair action

- 20 non-planar coils with systematic faults
- deep excavation of header area
- cracks and voids ← charged raisin
- repeated Paschen tests
- repeated full cold test

- Introduction
- Organisation of a big project - lessons learned
- Planning aspects - lessons learned
- Fabrication of components - lessons learned
- **Integration** - **lessons learned**
- Conclusions

Management of surprises

- the project must be prepared for surprises
- Risk identification and prevention required (mock-ups)
- in case of problems, clear procedures have to be available (CCB)

But: Work load and (limited) experience of the staff; complex priorities

Tolerances

- maximum possible tolerance allowable should be foreseen
- Fabrication and operation at the limits is costly and time-consuming

But: Physics requirements are usually high

Margins

- Margins and clearances should be as high as possible
- Fabrication and operation at technical limits is costly and time-consuming

But: Additional space is expensive; research facilities are complex and often at the technical limits


Forschungszentrum Jülich





Institute of Nuclear Physics Krakow




- 300 steel pipes and 24 superconducting bus-bars per module
- more than 500 welds and 24 superconducting joints per module
- three-dimensional stellarator geometry









Forschungszentrum Jülich



Institute of Nuclear Physics Krakow



- 300 steel pipes and 24 superconducting bus-bars per module
- more than 500 welds and 24 superconducting joints per module
- three-dimensional stellarator geometry
- motion of magnets for different magnetic configurations up to +/- 15mm
- complex system of clamps and holders, stiff and flexible at the same time
- intense metrology, demanding manufacturing, complex change management
- extremely limited available space in the cryostat \Leftarrow Design decision!

All projects have their individual history and development.

However, the main issues that have led to serious trouble in our project hold for any state-of-the-art fusion and non-fusion projects.

1. A competent project team must be available from the start, i.e. prior to design completion, component specification and start of procurement. Where the know-how is not available, strong external institutional partners must be found and deeply integrated into the project.
2. A lack of reasonable margins, clearances and tolerance levels implies an uncontrolled increase of complexity and frequent changes. This has a strong impact on time, costs and man-power.
3. Major components must be thoroughly tested (prototypes) and qualified prior to tender action. The manufacturing process must be accompanied by an intense QA program including a test program on manufacturing samples and mockups. Quality management must be involved in each single step. Trained inspectors must follow up manufacturing in detail.

4. A project needs a few persons who the device in all details. Experience with large construction projects is invaluable. Clear project structures and responsibilities are mandatory.
5. The project management must be able to identify risks precisely and timely enough to react with reasonable countermeasures. High-level management tools must be implemented and accepted on the working level. Formal procedures and written documents are unavoidable, but must be organized as pragmatic as possible.
6. Development and manufacturing risks should be taken to a large extent by the project. Industry cannot do that or will charge the project to cover unexpected costs, even beyond the contract. The only solution is to solve problems step-by-step with industry.
7. The construction of first-of-a-kind devices requires specialized in-house knowledge and specialized industrial suppliers. Often, a monopoly situation cannot be avoided and must be taken into account in design, planning and management. Loss of expertise may happen on short time-scale and must be checked.